

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20304-00-00
Spot: NESESESW Sec/Twnshp/Rge: 10-28S-29W
516 feet from S Section Line, 2368 feet from W Section Line
Lease Name: JANTZ TRUST Well #: 1-10
County: GRAY Total Vertical Depth: 5300 feet

Operator License No.: 7311
Op Name: SHAKESPEARE OIL CO., INC.
Address: 202 W MAIN ST
SALEM, IL 62881

String Size Depth (ft) Pulled (ft) Comments
SURF 8.625 350 WITH 210 SX CMT

172.25

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/26/2008 6:45 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: BILL CRAIG Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 840' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 390' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER WitnessType: NONE
Date/Time Plugging Completed: 06/26/2008 8:45 AM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 840' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 390' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

INVOICED
DATE 7-15-08
INV. NO. 2009060094

RECEIVED
KANSAS CORPORATION COMMISSION


JUN 30 2008

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01



Signed _____

[Signature]
(TECHNICIAN)

[Handwritten initials]