



15-163-20278-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gustus of Leben Drlg. has this
date requested permission to plug the following described well:

Mr. Gustus guarantees payment of the plugging fee.

Operator's full Name: Tilco, Etal

Complete Address: 200 Sutton Place, Wichita, Ks.

Lease Name: Becker "A" Well No. 1

Location: SE SE NE Sec. 34 Twp. 9 Rge. (E)(W) 16

County: Rooks Total Depth 3421 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Gustus was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Messers
Conservation Division Agent