

State of Kansas



15-163-20041-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS, 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

AUG 1 1967
8-1-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Radke of Garvey Drilling Co. has this date requested permission to plug the following described well:

Mr. Radke guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 6810 W. Highway 54 Wichita, Kansas

Lease Name: Kirkwood Well No. X-1

Location: Approx. S/2 S/2 NW Sec. 36 Twp. 9 Rge. 16 (E)(W) X

County Rooks Total Depth 3660 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Radke was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 550' and displace
35 sc cement thru drill pipe. Heavy mud to 260' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 3 sc cement.

Very truly yours,

Leo J. Messing
Conservation Division Agent