



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

15-163-21725-00-00

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Tim Scheck of Big Three Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: T & W Oil Co.

Complete Address: 400 E. 23st. Hays, Ks. 67601

Lease Name: NW SE SW Becher Well No. 1

Location: Rooks NW SE SW Sec. 19 Twp. 10 Rge. 17 (E) (W)

County: Rooks Total Depth: 3730'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Scheck was instructed to plug the well as follows:

8 5/8"-281' S.P. cuc. W/ 200 sacks common-2% Gel.-3% Cal.Cl.

Ordered 150 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" Plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 820' w/80 sacks cement,

2nd plug @ 300' w/40 sacks cement.

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole & 10 sacks in mouse hole.

Very truly yours,


Conservation Division Agent
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
07-12-1982
JUL 12 1982
CONSERVATION DIVISION
Wichita, Kansas