

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-163 - 30175-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JUN 14 1966  
06-14-1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Norwood of Leben Drilling Co. has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Bankoff & Leben

Complete Address: Box 2479 Tulsa, Okla.

Lease Name: Bice Well No. 1

Location: SE NW NE Sec. 2 Twp. 10 Rge 17 (E)(W) X

County Rooks Total Depth 3685 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540 Ft.  
and displace 25 sax cement thru drill pipe. Heavy mud to 190 Ft. set  
cementing plug and displace 20 sax cement thru drill pipe. Heavy mud  
to 40 Ft. set cementing plug, 1/3 sax hulls, and 10 sax cement to  
base of cellar. Plug rat hole with 2 sax cement.

Very truly yours,

[Signature]  
Conservation Division Agent