

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-163-30221-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Landis of Kern Drlg.Co. Inc. has this
date requested permission to plug the following described well:

Mr. Landis guarantees payment of the plugging fee.

Operator's full Name: Kern Drilling Co. Inc.

Complete Address: 337 Union Center Wichita, Kansas

Lease Name: Colby Well No. 1

Location: S/2 NW SW Sec. 27 Twp. 10 Rge. 17 (E)(W) X

County Rooks Total Depth 3598' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Landis was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and
displace 25 sc cement thru drill pipe. Heavy mud to 200' set cementing
plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set
cementing plug, 1/3 sc hulls and 10 sc cement to base of celler.

Plug rat hole with 2 sc cement

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

SEP 8 1966
09-08-1966
CONSERVATION DIVISION
Wichita, Kansas
[Signature]
Conservation Division Agent