

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

15-163-22009-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Rooks SEC. 6 TWP. 9S RGE. 19 E/W  
 Location as in quarters or footage from lines:

SE NW NW


Lease Owner Thornton E. Anderson

Lease Name McClellan Well No. 1

Office Address 840 First National Bank Bldg., Wichita, Ks.

Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole

Date Well Completed April 30, 1983

Application for plugging filed Yes

Plugging commenced April 29, 1983

Plugging completed April 30, 1983

Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hammel

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3595

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	287	8-5/8	287'	none

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Hole plugged with 170 sacks 50/50 pozmix, 4% gel, 3% CaCl  
 as follows:

1st plug @ 1556' with 20 sacks

2nd plug @ 780' with 80 sacks

3rd plug @ 330' with 40 sacks

4th plug @ 40' hulls with 10 sacks

10 sacks in rathole; 10 sacks in mousehole

Job completed at 1:30 a.m., April 30, 1983

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing

STATE OF KANSAS COUNTY OF SEDGWICK, ss. of Contractor for  
John Jay Darrah, Jr., President (~~employee of owner~~) or (~~owner or operator~~) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

RECEIVED  
 MAY 04 1983

(Signature) John Jay Darrah, Jr.

Mailard Drilling Co., Inc.  
405 Century Plaza, Wichita, Ks.  
 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 19 83

Dianne R. Fowler  
 Notary Public.

My Commission expires: August 25, 1984

15-163-22009-00-00

DRILLERS LOG

COMPANY: Thornton E. Anderson  
CONTRACTOR: MALLARD DRILLING CO., INC.  
405 Century Plaza  
Wichita, Kansas 67202

WELL NAME: McClellan #1  
DESCRIPTION:

SE NW NW 6-9S-19W

RIG NO.: 1

COUNTY: Rooks

TOTAL DEPTH: 3595'

ELEVATION: 2080 gr.; 2088 kb

COMMENCED: April 21, 1983

COMPLETED: April 30, 1983

CASING RECORD:


6 joints 8 5/8" 23# new surface

D & A


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, shale	0	1032	Ran 282' new 23# 8 5/8" surface casing; set and cemented at 287' with 180 sacks common cement, 3% CaCl, 2% gel. Cement circulated. Plug down @ 9:15 p.m. April 21, 1983. Ran 7 drillstem tests Hole plugged with 50/50 pozmix, 4% gel, 3% CaCl, as follows: 20 sacks @ 1556'; 80 sacks @ 780'; 40 sacks @ 330'; hulls and 10 sacks @ 40'; 10 sacks in rathole; 10 sacks in mousehole. Plugging completed 1:30 a.m. April 30, 1983.
Cedar hills sand	1032	1289	
Shale	1289	1556	
Anhydrite	1556	1590	
Shale	1590	2095	
Shale & lime	2095	2653	
Lime & shale	2653	3595	

STATE OF KANSAS )  
                          ) SS.  
COUNTY OF SEDGWICK )

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify that this is a true and correct copy of the log of the McCLELLAN #1 well, to the best of my knowledge.

  
John Jay Darrah, Jr., President

SUBSCRIBED AND SWORN to before me this 2nd day of May, 1983.

  
Dianne R. Fowler, Notary Public

My Commission Expires:  
August 25, 1984

RECEIVED  
STATE CORPORATION COMMISSION  
5-4-83  
MAY 04 1983  
CONSERVATION DIVISION  
Wichita, Kansas