

15-163-20877-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rooks County, Sec. 7 Twp. 9 Rge. 19W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW SE NE

Lease Owner Graham-Michaelis Corporation
Lease Name THOMAS Well No. 1-7
Office Address P. O. Box 247, Wichita, Kansas 67201
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed June 20 1979
Application for plugging filed (verbally) June 20 1979
Application for plugging approved (verbally) June 20 1979
Plugging commenced June 20 1979
Plugging completed June 20 1979
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3617'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD:

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 3617'

Set 1st plug at 770' with 70 sacks

2nd plug at 250' with 20 sacks

3rd plug at 40' solid bridge with 10 sacks
rathole with 5 sacks

Cemented with 50/50 posmix, 6% gel.

Plug was down at 1:00 a.m., 6-20-79

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1979

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet) 6-26-79
Name of Plugging Contractor Abercrombie Drilling, Inc

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 1979



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82



15-143-20877-0000

CONTRACTOR'S WELL LOG

OPERATOR: Graham-Michaelis Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Thomas #1-7
 LOCATION: SW SE NE, Section 7-9-19W
 Rooks County, Kansas
 SPUD DATE: June 12, 1979
 COMPLETION DATE: June 20, 1979

0	276	Shale and sand
276	1317	Sand and shale
1317	1506	Shale
1506	1543	Anhydrite
1543	1880	Shale
1880	2228	Shale and sand
2228	2407	Shale
2407	3361	Lime and shale
3361	3617	Lime
	3617	Rotary Total Depth

Spud hole at 8:45 p.m., June 12, 1979. Drilled 276' of 12 1/4" hole. Ran 8 joints of new 8-5/8" - 24# casing. Set at 275.79' with 200 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 6:15 a. m., June 13, 1979.

T.D. 3617'. Set 1st plug at 770' with 70 sacks, 2nd plug at 250' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Job was complete at 1:00 a.m., June 20, 1979.

SAMPLE TOPS:

Anhydrite 1506'
 B/Anhydrite 1543'

RECEIVED
 STATE CORPORATION COMMISSION

JUN 26 1979

CONSERVATION DIVISION
 Wichita, Kansas

6-26-79

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Thomas #1-7, SW SE NE, Section 7-9-19W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 22nd day of June, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.