


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-163-00489-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Rooks County, Sec. 29 Twp. 9 Rge. 19 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner Victor Drilling, Inc.  
Lease Name Deslongchamp Well No. 1  
Office Address 302 Koch Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry  
Date well completed 3-23-1953  
Application for plugging filed 3-23-19  
Application for plugging approved 3-23-19  
Plugging commenced 3-23-19  
Plugging completed 3-23-19  
Reason for abandonment of well or producing formation no shows



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3732 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	216	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy rotary mud from total depth of 3732 to 200 feet, bottom plug of 25 sx cement, filled with rotary mud to 40 feet, top plug with 10 sx cement.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Victor Drilling, Inc.  
Address 302 Koch Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Victor F. Reiserer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Victor F. Reiserer  
302 Koch Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 1953  
My commission expires 16-55



24-2675-B 2-52-20M

PLUGGING  
FILE SEC 22T 9 R 1954  
BOOK PAGE 28 LINE 12

RECEIVED  
STATE CORPORATION COMMISSION

APR 2 - 1953  
CONSERVATION DIVISION  
Wichita, Kansas

4-2-53

Victor Drilling, Inc.

No. 1 Deslongchamp

SE SE NW  
29-9S-19W

Spud: 3-12-53

Comp: 3-23-53

Rooks County

8 5/8" 216' w/115 sx

El. 2181 KB

sand & shale	0-216
shale	1060
Dakota sand	1220
sandy shale	1260
shale	1435
red bed & shale	1535
shale	1585
anhydrite	1628
shale	1835
shale & limestone	2470
lime	2615
shale & lime	2726
lime & shale	3267
lime	3314
lime & shale	3390
lime	3422
lime & shale	3437
lime	3471
hard LKC	3510
shale & lime	3553
lime	3574
shale & lime	3602
lime, shale & Conglomerate	3642
Conglomerate	3680
Arbuckle	3732
Total Depth	3732

ELECTRIC LOG TOPS

Topeka	3150
Heebner	3354
Toronto	3377
Lansing-Kansas City	3395
Base Kansas City	3610
Conglomerate	3640
Arbuckle	3678

STATE OF KANSAS )  
                          )SS.  
COUNTY OF SEDGWICK )

I, Victor F. Reiserer, swear that to the best of my knowledge the foregoing information is correct.

Victor F. Reiserer  
Victor F. Reiserer

Subscribed and sworn to before me, a Notary Public, this 31st day of March, 1953.

Alvin E. Ross  
Notary Public

My commission expires July 16, 1955.

**PLUGGING**  
FILE SEC 29T 9 R 192  
BOOK PAGE 28 LINE 12

4-2-53