

15-163-02882-00-00


WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

OR FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.



Rooks County. Sec. 29 Twp. 9 Rge. (E) 19 (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NW 1/4 SW 1/4 Lease Owner Petroleum Inc. & J.D. Ferrell Oil Co., Inc. Lease Name Des Marteau Desmarfeath Office Address Derby Bldg, Wichita, Kansas Well No. 1 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed Oct. 5 1948 Application for plugging filed 19 Application for plugging approved 19 Plugging commenced Oct. 6 1948 Plugging completed Oct. 6 1948 Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives Producing formation Depth to top Bottom Total Depth of Well Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: From 0 To 222 Size 8 5/8 Put In 9-25-48

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud - Set plug at 200' and cemented with 15 sax cement - Set plug at 30' cemented with 10 sax cement - cemented by Halliburton.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum Inc. Address Derby Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. J. W. Railsback (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Handwritten Signature] (Address)

SUBSCRIBED AND SWORN to before me this 15th day of Oct, 1948

My commission expires Oct, 15, 1957 Notary Public.



22-2625 2-48-15M



10-29-48

WELL LOG

Petroleum Inc.
~~Des Marteau #1~~
 Desmarteau ^{KU} TAP

Sec. 29 T. 9s R. 19 W
^{w/2} NW NW SW
 County: Rooks

Total Depth: 3659'
 Comm: 9-25-48 Comp: 10-5-48
 Contractor: J. D. Ferrell Drig. Co., Inc.
 Issued: 10-15-48 Rotary O-3659

Casing: 8 5/8" Set at 222' Elevation: 2141 D.F.
 Cemented with 100 sax Production: Dry
 cement - Cement Circulated

Figures Indicate bottom of Formations

cellar	4
clay & sopa stone	20
shale	190
shale & shells	222
shale	300
shale & sand	800
sand	930
shale, shells, sand	1080
dakota sand	1220
shale, shells, red bed	1545
lime	1585
shale & shells	2075
shale & lime	2225
shale & shells	2280
lime & shale	2335
lime	2380
shale & lime	2415
lime & shale	2525
shale & shells	2555
lime & shale	3265
lime	3339
lime & shale	3369
cherty lime	3385
lime	3624
lime, shale, chert	3659
Total Depth	3659

We hereby certify this to be a correct and accurate log of the above described well as shown by the Daily Drilling Reports.

J.D. FERRELL DRILLING COMPANY, INC.

By *J. D. Ferrell*

Subscribed and sworn to before me this 15th day of June, 1948.

My Commission expires:

Oct-15, 1951

Mark V. Sandberg
 Notary Public

PLUGGINGS
 REC SEC 29 T. 9 - R. 19 W
 WPK PAGE 6 LINE 11

10-29-48