


15-163-19185-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 29 Twp. 9S Rge. 19W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Century Production Company & K & E Drilling, Inc.
Lease Name Des Langchamp Deslangchamp Well No. 1
Office Address 719 Union Center
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 4, 1956 19
Application for plugging filed August 4, 1956 19
Application for plugging approved August 4, 1956 19
Plugging commenced August 4, 1956 19
Plugging completed August 4, 1956 19
Reason for abandonment of well or producing formation Commercial quantities of oil not found.
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	210'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 3637' to 200'
Set wooden plug and 1/2 sack hulls with 15 sacks cement
Filled hole with heavy mud to 40' and set with second plug and 1/2 sack hulls
Capped hole with 10 sacks cement



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E Drilling, Inc. 8-16-56
Address 719 Union Center

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale Silcott (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott

(Address) _____

SUBSCRIBED AND SWORN TO before me this 13th day of August, 1956

Coranne Shellcutt
Notary Public.

My commission expires June 1, 1960

PLUGGING
FILE SEC 29T 9 R 19W
BOOK PAGE 87 LINE 41

CENTURY PRODUCTION COMPANY - R & B DRILLING, INC.

THE NE 1/4 29-9S-19W
Rooks County, Kansas

Des Lanchamp No. 1

Des Lanchamp ^{KCC}
Commenced: July 28, 1956
Completed: August 4, 1956

Total Depth: 3637'

Casing
210' 8 5/8"

Cement
150 sacks

<u>Formation</u>	<u>Depth</u>
Clay and shale	0 - 110
Shale	110 - 650
Sand and shale	650 - 1040
Sand	1040 - 1275
Shale and shells	1275 - 1560
Antydrite	1560 - 1600
Shale and shells	1600 - 2145
Shale and lime	2145 - 3386
Lime	3386 - 3585
Conglomerate Shale	3585 - 3637

State of Kansas)
) ss.
Sedwick County)

I hereby certify that the above information is true and correct to the best of my knowledge.

Dale Silcott

Subscribed and sworn to before me this 9th day of August, 1956

Lorraine Shullcutt
Notary Public

Comm. expires:
June 1, 1960

8-14-56

PLUGGING
FILE SEC 29 T 9 R 19W
BOOK PAGE 87 LINE 41

NOTARY PUBLIC
Wichita, Kansas