


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Rooks County. Sec 29 Twp. 9S Rge. (E) 19 (W) W
Location as "NE/CNW/SW" or footage from lines 30' W. of NW NE NW
Lease Owner Clinton Oil Company
Lease Name DESLONGCHAMP Well No. 1-V
Office Address 6810 West Highway 54 - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-5 19 68
Application for plugging filed 12-5 19 68
Application for plugging approved 12-5 19 68
Plugging commenced 12-5 19 68
Plugging completed 12-5 19 68
Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.
If a producing well is abandoned, date of last production -- 19 --
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3625 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	216.65	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Set plug at 720' with 70 sacks 50-50 Pozmix, with 6% gel. Set plug at 210' with 20 sacks same. Set solid bridge and plug at 40' with 10 sacks. Plugging completed at 10:45 PM 12-5-68.

RECEIVED
STATE CORPORATION COMMISSION
DEC 13 1968
CONSERVATION DIVISION
Wichita, Kansas

12-13-68

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address 1425 Wichita Plaza - Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains
1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9 day of December, 19 68
My commission expires June 30, 1971

Sherry Gish Sherry Gish
Notary Public.



ROTARY DRILLING LOG

Operator: Clinton Oil Company
DESLONGCHAMP #1-V
30' W. of NW NE NW
Section 29-9S-19W
Rooks County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.

Commenced: 11-26-68
Completed: 12-5-68

Casing Record: 8-5/8" @ 216.65'
w/160 sx. Sunset
cement

Formations

Surface Clay	44'
Shale	1010'
Sand	1260'
Red Bed	1325'
Red Bed & Shale	1540'
Anhydrite	1581'
Shale	2100'
Lime and Shale	2395'
Shale and Lime	2430'
Lime and Shale	3130'
Lime and Shale	3155'
Lime	3625'
Rotary Total Depth (D & A)	3625'

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1968
CONSERVATION DIVISION
Wichita, Kansas

12-11-68

We certify the above log is
true and correct to the best
of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the
County of Sedgwick, State of Kansas, this 9th day of December, 1968.

Sherry Gish
Sherry Gish Notary Public



My Commission Expires:
June 30, 1971