

15-63-20796-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rooks County, Sec. 29 Twp. 9 Rge. 19  W  
Location as "NE/CNW/SW" or footage from lines  
SE NW NW


Lease Owner Icer Addis  
Lease Name Deslongchamp Well No. 1  
Office Address P.O. Drawer 8038 - Wichita, Ks. 67208  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole

Date Well completed May 10 1978  
Application for plugging filed May 10 1978  
Application for plugging approved May 10 1978  
Plugging commenced May 10 1978  
Plugging completed May 10 1978  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 3619  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud to 720' - plug with 70 sacks 50/50 pozmix, 6% Gel, thru drill pipe  
Mud to 185' with 20 sacks thru drill pipe.  
Mud to 40' - 1/2 sk hulls, plug & 10 sks. cement.;  
2 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 16 1978

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK SHEET)  
Name of Plugging Contractor Duke Drilling Co., Inc. 5-16-78


STATE OF Kansas COUNTY OF Barton, ss.  
Larry Curtis (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis  
Box 823 - Great Bend, Ks. 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of May, 19 78

Notary Public. *Deborah M. Hague*

My Commission expires 4-11-1982



19-163-20796-00-00

DRILLERS' WELL LOG

DATE COMMENCED: May 8, 1978  
DATE COMPLETED: May 10, 1978

Loer Addis  
DESLONGCHAMP #1  
SE NW NW Sec 29 - 9 - 19 W  
Rooks County, Ks.

ELEVATION: 2132 R.B.

FORMATION DATA

0 - 60'	Post Rock
60 - 204'	Shale
204 - 1260'	Shale & Sand
1260 - 1536'	Red Bed
1536 - 1576'	Anhydrite
1576 - 1722'	Red Bed
1722 - 3093'	Shale & Lime
3093 - 3301'	Lime
3301 - 3305'	Shale
3305 - 3323'	Lime & Shale
3323 - 3341'	Lime & Shale
3341 - 3561'	Lime
3561 - 3599'	Lime & Shale
3599 - 3619'	Dolomite
3619'	RTD

ANHYDRITE	1536
TOPEKA	3093
HEENEER	3301
TORONTO	3323
LANSING	3341
BASE K.C.	3561
AREUCKLE	3599
RTD	3619

Surface Pipe: Set used 8-5/8"  
28# at 204' with 150 sacks  
50/50 pozmix, 2% Gel, 3% cc.

AFFIDAVIT

STATE OF KANSAS  
COUNTY OF BARTON) ss.

Larry Curtis, of lawful age does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this \_\_\_\_\_ day of May 1978.

My Comm. Expires:  
April 11 1982

Dorothy M. Hague

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 16 1978  
CONSERVATION DIVISION  
Topeka, Kansas

5-16-78