

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 163-22595-00-00

LEASE NAME Thomas

WELL NUMBER #1-A

SPOT LOCATION 205' E SW SE SW

SEC. 35 TWP. 9 RGE. 19 (~~19~~ (W))

COUNTY Rooks

Date Well Completed 1-25-85

Plugging Commenced 1-25-85

Plugging Completed 1-26-85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Oil Property Management/Peregrine Energy

ADDRESS 221 N. Main, Suite 200-220, Wichita, KS 67202

(316) 263-0134

PHONE # (316) 262-0841 OPERATORS LICENSE NO. 5247/9639

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #7 (Gilbert Scheck, State Plugger)

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation None Depth to top NA bottom NA T.D. 3740

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To   | Size   | Put in | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
| Dakota    | Water   | 880  | 925  | 8-5/8" | 258'   |            |
| Topeka    | Water   | 3130 | 3350 |        |        |            |
| Lansing   | Water   | 3380 | 3600 |        |        |            |
| Arbuckle  | Water   | 3720 | TD   |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Well plugged with 200 sacks Haliburton 50/50 pozmix, 6% gel, 3% cc as follows: 20 sacks at 3740', 20 sacks at 1550', 100 sacks at 925', 40 sacks at 300', solid bridge and 10 sacks at 40' to surface, 10' sacks rat hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor H-30 Drilling Inc. License No. 5107

Address 250 N. Water, Suite 10, Wichita, KS 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Alan C. Snider (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 221 N. Main, Suite 220, Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 29 day of January, 19 85



Tammy P. Sheldon  
Notary Public

My Commission expires: February 24, 1988

Tammy P. Sheldon

RECEIVED  
STATE CORPORATION COMMISSION  
1-31-85  
JAN 31 1985  
CONSERVATION DIVISION  
Wichita, Kansas