


15-163-00764-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat.

Rooks County. Sec. 36 Twp. 9 Rge. 19 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Veeder Supply & Development Co.
Lease Name C. Mayhew Well No. 1
Office Address Box 201, Cherryvale, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 21, 1958 19
Application for plugging filed May 21, 1958 19
Application for plugging approved May 21, 1958 19
Plugging commenced May 21, 1958 19
Plugging completed May 21, 1958 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3836' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	219' w/125	sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 550' w/20 sacks cement; mud to 210'. Set plug and 1/2 sack hulls w/15 sacks cement; mud to 40'. Set plug and 1/2 sack hulls w/10 sacks cement. Cemented to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Veeder Supply and Development Co.
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
C. H. Woods (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Woods
Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of May, 19 58

July 11, 1960.




Leo Lawson Notary Public.
RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 36 T. 9 R. 19
BOOK PAGE 103 LINE 8

MAY 24 1958
CONSERVATION DIVISION
524-58

15-163-00764-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

A. F. Brann,

KLC 2AP

Drilled for Veeder Supply & Development Co. Farm C. Mayhew No. 1 Depth 3836'

Contractor Veeder Supply & Development Co. Pipe 219' 8 5/8" csg. w/125 sacks

Location SW/4 SW/4 SW/4 Sec. 36 Twp. 9 Range 19

Commenced 5-11-58 Completed 5-21-58 County Rooks State Kansas

Cellar, soil and shale	0	20	20	Elevation: ²¹⁹⁶ 3196'	RB
Sand and shale	20	130	110		
Shale, sand and gravel	130	185	55	Tops:	
Shale 185	219	34		Anhydrite	1592
Shale and shells	219	1150	931	Topeka	3163
Sand and shale	1150	1320	170	Heebner	3382
Sand, shale and red bed	1320	1592	272	Toronto	3405
Anhydrite	1592	1621	29	Ls. KC	3422
Shale and shells	1621	2000	379	Base KC	3639
Lime and shale	2000	2415	415	Conglomerate	3669
Shale, lime	2415	2520	105	Simpson Dolomite	3767
Lime	2520	2800	280	Arbuckle	3797
Lime and shale	2800	3235	435		
Shale lime	3235	3297	62		
Lime	3297	3682	385		
Conglomerate	3682	3767	85		
Simpson	3767	3797	30		
Arbuckle	3797	3836	39		
T. D.	3836				

AFFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above drilling log covering the Mayhew #1 well located in Section 36-9-19, Rooks County, Kansas, and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By C. H. Woods
C. H. Woods

Subscribed and sworn to before me this 23rd day of May, 1958.

C. H. Lawson
Notary Public

My commission expires July 11, 1960.



RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1958

CONSERVATION DIVISION
Wichita, Kansas

5-24-58

PLUGGING
SEC. 36 T. 9 R. 19W
BOOK PAGE 103 LINE 8