


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-163-00917-0000

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 36 Twp. 9 Rge. 19 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines C SE NE
Lease Owner Grant Oil Company
Lease Name Mosher Well No. 1
Office Address: 518 Board of Trade Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-31 19 59
Application for plugging filed 5-31 19 59
Application for plugging approved 5-31 19 59
Plugging commenced 7:30 P.M. 5-31 19 59
Plugging completed 10:00 P.M. 5-31 19 59
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Fabricus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3770 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	220	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 500'. Set plug. Mixed 20 sacks cement by hand, poured same through drill pipe.

Filled hole with heavy rotary mud to 210'. Dumped in 1/3 sack hulls. Set plug. Mixed 20 sacks cement by hand, poured same through drill pipe.

Filled hole with heavy rotary mud to 40'. Dumped in 1/3 sack hulls. Set plug. Mixed 10 sacks. Filled hole to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1959

CONSERVATION DIVISION
Wichita, Kansas 65-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas COUNTY OF Barton
S. C. Lingreen ^{SS} Drilling Contractor
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. C. Lingreen
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of June 1959
My commission expires 6-25-59
Kenneth G. Fischer Notary Public.

PLUGGING
FILE SEC 36 T. 9 R. 19 W
BOOK PAGE 42 LINE 42

15-163-00917-00-00

DRILLERS' LOG

Mosher No. 1
Loc: C SE NE
Sec: 36-9S-19W
Rooks County, Kansas
Company: Grant Oil Company, et al
Contractor: Honaker-Davis Drlg. Co.

Comm: 5-22-59
Comp: 5-31-59
Rotary Total Depth: 3770'
Casing: 8-5/8" at 220'
D & A

0	40	Top soil & clay	
40	175	Post rock, sand & clay	
175	220	Blue shale	8-5/8" casing cemented at
220	1050	Shale	220' with 185 sacks cement
1050	1250	Sand	and 4 sacks calcium chloride.
1250	1595	Shale & Red Bed	
1595	1634	Anhydrite	
1634	2100	Shale & Red Bed	
2100	2790	Lime & Shale	
2790	2807	Lime	
2807	3650	Lime & Shale	
3650	3770	Lime, Shale & Chert	
3770		Total Rotary Depth	D & A


RECEIVED
STATE CORPORATION COMMISSION
6-5-59
JUN 5 1959
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is the true and correct copy of the above log to the best of my knowledge.



H. S. Forbes

Subscribed and sworn to before me this 3rd day of June, 1959.



Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING
FILE SEG 36 T. 9 R. 19W
BOOK PAGE 42 LINE 42