


15-163-00542-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 1 Twp. 9 Rge. 20 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines SW SW SE
Lease Owner Trans Era Petroleum, Inc.
Lease Name Anderson Anderson ^{KCC} _{APP} Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 8/23/53 19
Application for plugging filed 8/22/53 19
Application for plugging approved 8/22/53 19
Plugging commenced 8/22/53 19
Plugging completed 8/22/53 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Pettyh
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3662 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	178	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 170'. Wouldn't plug. 15 sacks of cement mixed and poured through drill pipe. Filled hole with mud to 40'. Wouldn't plug then 1/2 sacks of hulls and 10 sacks cement on top of hulls. Anchored to rotary table.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Michaelis
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28th day of August, 19 53

My commission expires 1-30-57
Margie Cooper Notary Public.

NOTARY PUBLIC seal for Margie Cooper, commission expires 1-30-57.

RECEIVED stamp: STATE CORPORATION COMMISSION, SEP - 3 1953, 9-3-53, WICHITA, KANSAS.

PLUGGING stamp: FILED SEP 21 1953, R206, BOOK PAGE 124 LINE 35.

15-163-00542-00-00

Trans Era Petroleum, Inc.
Anderson #1
Anderson ^{KCC} _{ZAP}
Total Depth: 3662
Comm. 8/6/53
Comp. 8/23/53

SW SW SE 1-9-20W
Rooks County, Kansas

Casing
8 5/8" Set @ 178'

Cement
130 sacks of L. S.

Formation	Depth
Shale	625
Sand & Shale	840
Sand	950
Shale & shells	1060
Sand	1295
Shale & shells	1305
Shale & red bed - sand	1500
Shale & shells - sand	1565
Anhydrite	1615
Shale & red bed	1710
Shale & shells	1905
Shale & shells & lime	2190
Lime & shale	2335
Lime	2417
Shale & lime	2595
Lime	3305
Lime & shale	3335
Lime	3445
Lime & shale	3618
Broken Lime & Dolomite	3630
Arbuckle	3655
Lime	3662'

STATE OF KANSAS)
) SS:
RUSSELL COUNTY)


I hereby certify that the above information is true and correct to the best of my knowledge.

A.R. Michalski

Subscribed and sworn to before me this 28th day of August, 1953

Margie Cooper
Notary Public

My commission expires: 1-30-57.



RECEIVED
CORPORATION COMMISSION
SEP 10 1953 9-10-53
CONSER

PLUGGING
FILE SEC 1-T-9-R20u
BOOK PAGE 124 LINE 35