

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION JUN 26 2008  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD CONSERVATION DIVISION  
K.A.R. 82-3-117 WICHITA, KS

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: LARSON OPERATING COMPANY  
Address: 562 W. STATE RD 4 OLMITZ, KS 67564  
Phone: 620-653-7368 Operator License #: 3842  
Type of Well: OIL Docket #: \_\_\_\_\_  
(Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)  
The plugging proposal was approved on: 6/6/2008 (Date)  
by: CASE MORRIS (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
ARBUCKLE OPEN HOLE Depth to Top: 3280' Bottom: 3305' T.D. 3305'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-009-16369-00-00  
Lease Name: SCHNEIDER "B"  
Well Number: 4  
Spot Location (QQQQ): \_\_\_\_\_ - SE - NE - NW  
990 Feet from  North /  South Section Line  
2310 Feet from  East /  West Section Line  
Sec. 1 Twp. 16 S. R. 14  East  West  
County: BARTON  
Date Well Completed: SPUDDED 11/9/1937  
Plugging Commenced: 6/23/2008  
Plugging Completed: 6/23/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
ARBUCKLE	OIL	0	639'	10-3/4"	639'	0'
		0	3280'	7"	3280'	0
		0	3277'	5-1/2"	3277'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same, depth placed from (bottom), to (top) for each plug set.

Perf sqz holes @ 1550-51', 850-51' & 150-51', 3 jspf. TIH w/ tbg to 3288'. RU Allied. Spotted 11 sx gel & 75 sx cmt w/ 300# hulls.  
Pulled tbg to 1564' & spotted 100 sx cmt. Pulled tbg to 752 & circ cmt to surface w/ 50 sx. TOH w/ tbg. Tied on to csg & pumped  
225 sx cmt @ 500# - circ cmt up annulus to surface. SI csg w/ 0#. Plugged w/ 11 sx gel, 300# hulls & 400 sx 60-40 poz w/ 4% gel.  
Plugging complete @ 8:00 pm, 6-23-08. State man on loc - Bruce Rodie.

Name of Plugging Contractor: EXPRESS WELL SERVICE & SUPPLY, INC. License #: 6426  
Address: P.O. BOX 19 VICTORIA, KS 67671-0019  
Name of Party Responsible for Plugging Fees: LARSON OPERATING COMPANY, A DIVISION OF LARSON ENGINEERING, INC.  
State of KANSAS County, BARTON, ss.

CAROL LARSON (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Carol Larson SECRETARY/TREASURER  
(Address) 562 WEST HIGHWAY 4 OLMITZ, KS 67564-8561

**DEBRA J. LUDWIG**  
Notary Public - State of Kansas  
My Appt. Expires 5/5/2012

SUBSCRIBED and SWORN TO before me this 24TH day of JUNE, 2008  
Debra Ludwig My Commission Expires: 5/5/2012  
Notary Public