

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Daystar Petroleum, Inc.
Address: P.O. Box 360 Valley Center, KS 67147-0360
Phone: (620) 793-2757 Operator License #: 30931
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-079-20629-00-01
Lease Name: Ediger A
Well Number: 2
Spot Location (OQQQ): W2 S2 N1/2 SE NE
2970 Feet from North / South Section Line
550 Feet from East / West Section Line
Sec. 21 Twp. 22 S. R. 3 East West
County: Harvey
Date Well Completed: _____
Plugging Commenced: 5-30-08
Plugging Completed: 6-3-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	From	To	Size	Put In / Pulled Out
				8-5/8"	260' / None
				4-1/2"	3765' / 1981'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed. from _____ feet to _____ feet each set.
Removed 4-1/2" casing slips, stretched pipe & gained 7" of stretch. Set cast iron bridge @ 3650', dumped 2sx. cement on top of plug. Shot pipe @ 1981', came loose. Pulled 1460' out of hole, stopping @ 500'. Pumped 500lbs. hulls & 35sx. cement. Pulled 190' out, stopping @ 310'. Circulated with 100lbs. hulls & 225sx. cement. Plugging complete.

Name of Plugging Contractor: Gressel Oilfield Service Inc
Mike's Testing & Salvage, Inc. License #: 31529 3004
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Daystar Petroleum, Inc.
State of Kansas County: Rice ss.


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 1st day of July 2008

Irene Herzberg
Notary Public My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 02 2008
CONSERVATION DIVISION
WICHITA, KS

Handwritten initials