

State of Kansas



15-163-00389-00-01

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 3 1969
 CONSERVATION DIVISION
 Wichita, Kansas

2-3-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Parks of Gabbert Jones, Inc. has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton

Complete Address: 800 Sutton Place Wichita, Ks.

Lease Name: Celina Well No. 1

Location: SE SE SW Sec. 21 Twp. 9 Rge. 19 (E)(W) XX

County: Rooks Total Depth 3693 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Parks was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace 70 sk cement thru drill pipe. Heavy mud to 210' set cementing plug and displace 20 sk cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hills and 10 sk cement to base of cellar. Plug rat hole with 2 sk cement.

Very truly yours,

Geo F. Massey
 Conservation Division Agent