



15-163-20159-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. - 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

12-9-68  
RECEIVED  
OIL & NATURAL GAS COMMISSION  
DEC 9 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Rodie of Rains & Williamson, Inc. has this date requested permission to plug the following described well:

Mr. Rodie guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Co.

Complete Address: 6810 West Highway 54, Wichita, Ks.

Lease Name: Deslogchamp Well No. 1 - V

Location: NW NE NW Sec. 29 Twp. 9 Rge. 19 (E)(W) XX

County: Rooks Total Depth 3625 Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost-Hole       

Mr. Rodie was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace  
70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Leo F. Massey  
Conservation Division Agent