



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 5-21-58, 19 , authorized the following plugging operation:

Operator's Full Name: Veeder Supply & Dev Co

Complete Address: Box 201 Cherryvale, Kans

Lease Name: ^{KCC 2AP} C. Mayhew Well No. 1

Location: SW SW SW Sec. 36 Twp. 9 Rge. 19 (E) (W)

County: Rooks Total Depth: 3836

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pipe, circulate with heavy mud, set plug at 550' - 20 sax
cement through drill pipe, mud to 210', set plug, 1/2 sack hulls and
15 sax cement, mud to 40', set plug, 1/2 sack hulls and 10 sax cement.

Very truly yours,

Signed: Jewel M. Ogden
 Conservation Division Agent

6-2-58