

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-19361-00-00

JUL 6 1964
06-06-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc
Complete Address: R R # 2 Great Bend, Kansas
Lease Name Wilson Well No. A*C # 1
Location SW SW SE Sec. 34 Twp. 10 Rge. (E) (W) 18
County Rooks Total Depth 3620
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Southwest Casing Pulling
Address: Great Bend, Kans License No. 399
Operation Completed: Hour 4PM Day 3 Month 7 Year 64

The Above well was plugged as follows:

8 5/8" 256' circulated with cement - 4 1/2" 3434 with 225 sax cement
PB 3351' Perforated 3279.

Sand back to 3260', set 3 sax cement with dump bailer - pulled 2500'
4 1/2" to 600' - circulated hole with heavy mud through 4 1/2" at 600'
(25 sax Gel) - displaced 20 sax cement through 4 1/2" at 600', heavy mud to
200', displaced 20 sax cement through 4 1/2" at 200', heavy mud to 35'
cement 35' to 0'

Mudding and cementing by Southwest Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edna Kelly*
Well Plugging Supervisor

DATE 7/6/64
INV. NO. 9405-w