

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-03007-00-00

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1964
12-22-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc

Complete Address: Route #2 Great Bend, Kansas

Lease Name Wilson Well No. A-2

Location SE SE SE Sec. 35 Twp. 10 Rge. (E) (W) 18

County Rooks Total Depth 3674

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith & Globe Cementing Co

Address: Ellinwood, Kans License No. 396

Operation Completed: Hour 4PM Day 20 Month 12 Year 64

The Above well was plugged as follows:

8 5/8" 235' circulated with cement - 5 1/2" 3673' with 125 sax cement - hole in 5 1/2" at 1028' - circulated 5 1/2" from 1028' to 0' with 425 sax cement - 50% stratacrete - no pipe recovery. 5 1/2" Perf at 3272'

Pumped hole full heavy gel mud (35 sax Gel), pumped wiper plug followed by 70 sax cement.

Cementing by Globe Cementing Co. 700# Pump Pressure on Mudding 350# cementing.

I hereby certify that the above well was plugged as herein stated.

DATE 12/23/64
INV. NO. 389-W

Signed: Leon Petty
Well Plugging Supervisor