

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock,  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-163-01884-00-00 (of this well)

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Wilson "B" Well No. 1

Location SE SE SW Sec. 35 Twp. 10 Rge. (E) (W) 18

County ~~Sevier~~ Rocks Total Depth 3648'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 4 P Day 15 Month 6 Year 1978

The above well was plugged as follows:

Total Depth 3648' 8. 5/8 csg set 1408' cwc 500 sk.

5 1/2 csg set 3639' cw 150 sk cem.

5 1/2 csg sq. at 2008' & circ. to surface. No pipe recovered.

5 1/2 csg perf. (3538'-3251')

Set 5 1/2 wood plug at 3550' -poured sand (3550'-3230') dumped 4 sk cem. W/dump bailer.

Filled 5 1/2 csg with mud to 615' -set rock & sand bridge (615'-600')

Filled with RMC from 615' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
06-21-1978  
JUN 21 1978

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 6-26-78

INV. NO. 1563.0