

KANSAS
STATE CORPORATION COMMISSION

R

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-63196-00-00

File No. 104-42 County: _____ Rooks
Location: SE SW SW Sec. 35 Twp. 10 Rge. 18 (E) (W)
Name of Field: ~~Wilson~~ Total Depth: 3606

I have this date completed supervision of plugging of:

Lease Name: Wilson Well No. 1

Operator's Full Name: Continental Oil Co

Complete Address: Box 98 Plainville, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 8 Month 7 Year 58

The above well was plugged as follows:

10 3/4" at 200' circulated with cement - 6" 3604 cemented & squeezed at 850' with 200 sax cement.

Filled with sand to 3320', set 4 sax cement with dump bailer, pulled 712' 6" to 600', circulated hole with heavy mud through 6" (Aquagel), displaced 25 sax cement through 6" at 550', heavy mud to 190', displaced 20 sax cement through 6" at 190', heavy mud to 30', set rock and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co pump truck.

Signed: *Jewel M. Ogden*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

STATE CORPORATION COMMISSION
JUL 17 1958
07-17-1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 35 T. 10 R. 18 W.
BOOK PAGE 104 LINE 42