

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-30137-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
01-18-1971

Operator's Full Name Dave Collins Universal Well Service

Complete Address 300 S. Wyoming Plainville, Kansas 67663

Lease Name Mayhew Well No. 1

Location SE SW SE Sec. 1 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3740'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11:30A Day 14 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 3740' 8 5/8 csg set at 196' cwc 125 sk.

4 1/2 csg set at 3739' cw 150 sk cmt.

4 1/2 csg PBSD 3514' with top perf. (3390')

Filled 4 1/2 csg W/sd (3375-3514) Dumped 4 sk cmt W/dump bailer. (3335-3375)

Cutoff and recovered 796' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel W/5 sk hulls - 70 sk poz 6% - 8 sk gel -

released plug and pumped 50 sk poz 6%. Max. pres. 600 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo P. Massey  
Well Plugging Supervisor

DATE 1/18/71  
INV. NO. 3221-W