

K  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-163-19362-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
07-16-1962  
JUL 16 1962  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Davis Bros  
Complete Address: 510 Mc Farlin Bldg Tulsa, Okla  
Lease Name Mayhew Well No. 1-B  
Location CSW SE Sec. 1 Twp. 10 Rge. (E) (W) 19  
County Rooks Total Depth 3759  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated: Lost hole - dropped pipe  
Plugging Contractor: Transit Corp & Halliburton Cementing Co  
Address: Oklahoma City, Okla License No.       
Operation Completed: Hour 9AM Day 10 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 165' circulated with cement.  
Dropped 4 1/2" while trying to set pipe - 1800' lost in hole - circulated hole with mud, displaced 25 sax cement through drill pipe at 1900', heavy mud to 550', displaced 20 sax cement through drill pipe; heavy mud to 180' set plug and displaced 20 sax cement through drill pipe, heavy mud to 35' set plug, hulls and filled to bottom cellar with cement.

Cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 7/17/62  
INV. NO. 5381-W