

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-163-19363-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1964
10-19-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Davis Bros
Complete Address: 510 Mc Farlin Bldg Tulsa, Okla
Lease Name Mayhew (B) Well No. A-1
Location CSW SE Sec. 1 Twp. 10 Rge. (E) (W) 19
County Rooks Total Depth 3690
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Barnes & Sons & Globe Cementing Co
Address: Russell, Kans License No. 9
Operation Completed: Hour 3PM Day 16 Month 10 Year 64

The Above well was plugged as follows:

8 5/8" 172' circulated with cement - 4 1/2" 3688' with 275 sax cement -
PB 3452' - perf 3444'
Filled with sand to 3430', set 4 sax cement with dump bailer - pulled
2390' 4 1/2" to 550', pumped 20 sax gel at 550' - hole pressured up - pulled
4 1/2" to 490' - hole pressured up - pulled pipe to 400', circulated hole
with heavy gel mud (30 sax Gel), displaced 20 sax cement through 4 1/2" at
400', heavy mud to 180', displaced 20 sax cement through 4 1/2" at 180', heavy
mud to 35', cement 35' to 0'.

Mudding and cementing by Globe Cementing Co,

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/19/64

INV. NO. 2-W

Signed: Edward Lee
Well Plugging Supervisor