

KANSAS

*SL*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20299-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 11 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
03-11-1970

Operator's Full Name Donald C. Slawson

Complete Address 408 One Twenty Bldg., Wichita, Kansas

Lease Name Smee "A" Well No. 1

Location NW NE NW Sec. 2 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3700

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Go. Tools

Address        License No.       

Operation Completed: Hour 1A Day 7 Month 3 Year 1970

The above well was plugged as follows:

RTD 3700' 8 5/8 csg set at 240' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3/11/70  
INV. NO. 1576-W

Signed: Leo F. Mussey  
Well Plugging Supervisor