

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163--21,476-06-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Graves Drilling Company

Complete Address 910 Union Center, Wichita, Kansas 67202

Lease Name Smee Well No. #2

Location SW-NE-NW Sec. 2 Twp. 10S Rge. 19 (East) (West)

County Rooks Total Depth 3700'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Pioneer Drilling Company, Inc.

Address 308 W. Mill St., Plainville, Kansas 67663 License No. _____

Operation Completed: Hour: 9:5AM. Day: 15th Month: Nov. Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-210' s.p. cuc. w/125 sacks common cement-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 840' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulated with 10 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
11-23-1981
NOV 25 1981

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 12-11-81

INV. NO. 8682-w