

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-~~01915~~ 01915-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1970
CONSERVATION DIVISION
Wichita, Kansas
09-14-1970

Operator's Full Name Kewange Oil Company

Complete Address P. O. Box 360 Hoisington, Kansas 67544

Lease Name Husted "B" Well No. 1

Location NE SE SW Sec. 11 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3588'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 12 N Day 12 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3588' 8 5/8 csg set at 1450' cwc 700 sk.

5 1/2 csg set at 3583' cw 200 sk cmt.

5 1/2 csg perf. (3175-3180)

Filled 5 1/2 csg W/sd (3560-3588') Dumped 4 sk cmt W/dump bailer. (3535-3560)

Set 5 1/2 wood plug at 3100' poured 10' sd and dumped 4 sk cmt W/dump bailer. (3060-3100)

Recovered 2598' of 5 1/2 csg.

Mud to 700' - 15' rock and 3 yds readymix cmt. (480-700)

Mud to 220' - 10' rock and 3 yds readymix cmt. (0-220)

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. J. Marney
Well Plugging Supervisor

INVOICED
DATE 9-14-70
INV. NO. 2526-W