

KANSAS

24

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-01914-00-00

Operator's Full Name Kewanee Oil Company

Complete Address P. O. Box 360 Hoisington, Kansas 67544

Lease Name Husted "A" Well No. 2

Location SW NW SE Sec. 11 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3571

Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 3: P Day 9 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3571' 8 5/8 csg set at 1435' cwc

5 1/2 csg set at 3569' cw 125 sk cmt.

5 1/2 csg perf. (3154)

Filled 5 1/2 csg W/sd (3550-3571) Dumped 4 sk cmt W/dump bailer. (3520-3550)

Set 5 1/2 wood plug at 3100' -- poured 10' sd and dumped 4 sk cmt W/dump bailer. (3050-3100)

Cutoff and recovered 2165' of 5 1/2 csg.

Mud to 620' set 15' rock and 3 yds readymix cmt. (400-620)

Mud to 220' set 15' rock and 3 yds readymix cmt. (0-220)

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
09-11-1970
SEP 11 1970

Signed: Leo J. Manning
Well Plugging Supervisor

DATE 9/11/70

INV. NO. 2509-11 CONSERVATION DIVISION
Wichita, Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

15-163-01914-00-00

August 7, 1970

WELL PLUGGING AUTHORITY

Well No.	2
Lease	Husted "A"
Description	SW NW SE 11-10-19W
County	Rooks
Total Depth	3571
Plugging Contractor	?

Kewanee Oil Company
P. O. Box 360
Hoisington, Kansas 67544

Gentlemen: :

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

J. Lewis Brock
J. Lewis Brock, Administrator

Mr. Leo Massey Box 582 Hays, Kansas

is hereby assigned to supervise the plugging of the above named well.

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1970

CONSERVATION DIVISION
Wichita, Kansas

09-11-1970