

15-163-01915-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kewanee Oil Company

Complete Address P.O. Box 360 Hoisington, Kansas 67544

Lease Name Husted "B" Well No. 2

Location SE NE SW Sec. 11 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3615

Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 2:30 P Day 9 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3615' 8 5/8 csg set at 200' cwc

5 1/2 csg set at 3611' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3600-3615) Dumped 5 sk cmt W/dump bailer. (3560-3600)

Cutoff and recovered 2494' of 5 1/2 csg.

Pumped down 8 5/8 csg with 22 sk gel W/4 sk hulls, 70 sk 6% poz, 8 sk gel, plug and 50 sk poz 6%.

Cmt (0-210) gel (210-450) cmt (450-660) gel (660-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED RECEIVED
STATE CORPORATION COMMISSION
09-11-1970
SEP 11 1970
CONSERVATION DIVISION
Wichita, Kansas

Signed: Leo F. Massing
Well Plugging Supervisor

DATE 9/11/70
INV. NO. 2510-4