

*70*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

*15-163-20414-00-00*

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 8 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
*02-08-1972*

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Shields Building, Russell, Kansas 67665

Lease Name Husted Well No. 1

Location SW NE SE Sec. 11 Twp. 10 Rge. (E) (W) 19

County \_\_\_\_\_ Rooks: \_\_\_\_\_ Total Depth 3648'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A XX

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Co. Tools

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 10:15 A Day 2 Month 2 Year 1972

The above well was plugged as follows:

RTD 3648' 8 5/8 csg set at 222' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 2/11/72  
INV. NO. 5160-W

Signed: Fred A. Massey  
Well Plugging Supervisor