

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03208-00-00
Spot: CE2SWNE Sec/Twnshp/Rge: 6-9S-17W
3300 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: GARVERT Well Number: 2
County: ROOKS Total Vertical Depth: 3354 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3354 75 SX CMT
Surface Casing Size: 8.625 feet: 166 125 SX CMT

\$109.01

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2003 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 210 sxs Swift Multi Density Cement with 500# hulls.
Squeeze records: 737' w/300 sxs. 805' w/350 sxs. 910' w/75 sxs.
Packer at 3040'. Tubing parted at 2884'. Top of rods at 2600'.
Perforations: open hole 3354'-3357'. Top LKC perf 3072'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/18/2003 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2431'. Swift Services pumped 20 sxs cement, followed with 30 sxs with 400# hulls.
Pulled tubing to 1326'. Swift Services pumped 75 sxs cement with 100# hulls - circulated cement.
PTOH. Squeezed with 50 sxs cement.
Max. P.S.I. 400#. S.I.P. 300#.
Hooked up to backside - pumped 35 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.

RECEIVED
APR 28 2003
KCC WICHITA
4/28/03

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

4-29-03

INV. NO.

2003061472

Form CP-2/3

APR 23 2003

TRANS ERA & OIL TRADING #2 GARVET

6-9-17W
E2 SW NE

Contr. _____ ROOKS County

E 19 1/4 RB Comm. _____ Comp. 12-31-54 IP 960 BOPD

Tops	Depth	Datum	Casing
ANH	1250	69 1/2	8" 166
			5" 3353
HEEB	3049	-1105	
TOR	3069	-1125	DST 3129-39/1 HR, 65' MDY
LANS	3092	-1148	SLT WTR, BHP 1125#
			DP: CO 3354; 300' OIH/2 HR
			SWB 25 BOPH, NW
ARB	3352	-1408	
ID	3354	-1410	

DOPITA POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS