

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22643-00-00  
Spot: S2NENENE Sec/Twnshp/Rge: 6-9S-17W  
4785 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: GARVERT Well Number: 8  
County: ROOKS Total Vertical Depth: 3376 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3414 200 SX CMT  
Surface Casing Size: 8.625 feet: 218 145 SX CMT

\$109.72

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/14/2003 8:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 200 sxs cement and 500# hulls.  
D.V. Tool at 1321' w/400 sxs.  
Fluid level 500'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/14/2003 10:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2500'.  
Swift Services pumped 72 sxs with 450# hulls.  
Pulled tubing to 1300' - circulated with 90 sxs cement with 50# hulls.  
PTOH. Squeezed with 10 sxs cement. S.I.P. 300#.  
Hooked up to backside. Pumped 3 sxs cement. S.I.P. 500#.  
D.V. Tool 1321' cwc with 400 sxs.

RECEIVED  
APR 18 2003  
KCC WICHITA 4/18/03

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-21-03  
INV. NO. 2003061424

APR 14 2003

MURFIN DRILLING COMPANY

250 N. WATER, #300

#8 GARVERT

6-9-17W

C S/2 NE NE NE


WICHITA, KS 67202

CONTR COMPANY TOOLS

CTY ROOKS

GEOL RICH BELL

FIELD DOPITA



ELV 1976 KB SPD 4/9/85 CARD ISSUED 6/6/85 IP P 16 BO & 50 BWPD  
1971 GL DRLG COMP 4/14/85 LKC 3124-3350 OA

LOG	Tops	Depth/Datum
ANH	.....	1279+ 697
B/ANH	.....	1313+ 663
TOP	.....	2866- 890
HEEB	.....	3083-1107
TOR	.....	3105-1129
LANS	.....	3124-1148
BKC	.....	3351-1375
ARB	.....	3405-1429
LTD&RTD	.....	3415-1439

API 15-163-22,643

8 5/8 " 218 / 145SX, 5 1/2 " 3414 / 600SX  
DST (1) 3018-60 (TOP) / 30-45-60-90, REC 10' SLI OIL SPKD  
MW, 720' MSW, SIP 1219-1219#, FP 135-193 / 240-365#, BHT  
103°  
MICT - CO, PF (LKC) 3348-50, W / 4 SPF, AC 120G (MOD-202),  
SWB DWN, SO, PF (LANS) 3323-25, W / 4 SPF, AC 190G (MOD-  
202), SWB DWN, SO, PF (LKC) 3284-86, W / 4 SPF, AC 280G  
(MOD-202), SWB DWN, SO, PF (LKC) 3222-26, W / 4 SPF, AC  
380G (MOD-202), SWB DWN, SO, PF (LKC) 3167-70 & 3124-26,  
W / 4 SPF, AC 520G (MOD-202), SWB DWN, SO, SET 2 1/2 "  
TBG AT 3352', POP, P 16 BO & 50 BWPD, 5/11/85

COPYRIGHT 1985  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS