

C

3-30

6 041032

API NUMBER 15- 163-23,038 ~~0000~~

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW SE, SEC. 6, T. 9 S, R. 17 W/E
2310 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5537

Lease Name Moos Well # 4

Operator: Kenny Brown Ent.
Name & Address: 401 N. Washington
Box 340
Plainville, Ks. 67663

County Rooks 68.25
Well Total Depth 2100 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 212 w/135 sk

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cement License Number _____

Address _____ Hays, Ks.

Company to plug at: Hour: 10:30AM Day: _____ Month: _____ Year: 19 89

Plugging proposal received from Mike Waggoner

(company name) Red Tiger Drilling (phone) _____

were: Ordered 400skb 65/35 Poz 6% Gel 2% C C w/1/4# F.C.

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1989
5/10/89
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30AM Day: 30 Month: March Year: 19 89

ACTUAL PLUGGING REPORT Mar 29, 1989 spotted 50 sks cement at 2100'. Spotted 50

sks cement at 1270'; Wait 3-4 hrs. Spotted 100 sks cement at 730'; pulled d.p.,
wait 12 hrs. for cement to set. March 30, 1989 tagged top of cement at 1181'
(15,000#) circ. heavy mud, pulled d.p. to 730'; spotted 100 sks cement at 730';
pulled d.p. to 270'. spotted 50 sks cement; pulled d.p. topped w/15 sks cement to
surface: ck. t.o.c. April 6, 1989 at 14'. circ 15 sks cement in rathole.

Remarks: Lost circ at 1590' -1605'; cavity at salt sec.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Dennis L. Hamel (TECHNICIAN)
Dennis Hamel

INVOICED
DATE 5-10-89
INV. NO. 24755