

Received 5/18/95

3-20 4-041677

API number: 15-163-30339-00-02  
3-1959

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 S. MARKET, ROOM #2078  
WICHITA, KANSAS 67202

NE /4 SEC. 06, 09 S, 17 W  
2970 feet from S section line  
330 feet from E section line

Operator license# 30606 Lease Garvert well # 4

Operator: Murfin Drilling Company, Inc. County Rooks 112.13

Address: 250 N. Water Well total depth 3450 feet  
Suite #300 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 173 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: 250 N. Water - Suite #300 - Wichita, Kansas 67202

Company to plug at: Hour: 9:00A.M. Day: 20 Month: March Year: 95

Plugging proposal received from: John Gerstner

Company: SAME Phone: \_\_\_\_\_

Were: 5 1/2" casing set at 3448' w/150 sxs. cement. Perf. at 3215' - 3312'. Salt @ 2150' - Anhy. @ 1400' - Dakota @ 800'. 30 sxs. cement pumped down annulus on March 16, 1966. Order 350 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls. Perforate at 2150' - 1400' - 800'.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:30P.M., Day: 20, Month: March, Year: 95

Actual plugging report: Checked 8 5/8" - pumped 5 sxs. 60/40 pozmix - 10% gel. Max. P.S.I. 300# held. On March 16, 1966, 30 sxs. was pumped down 8 5/8". Ran tubing in 5 1/2" casing to 2500' on September 26, 1970. 30 sxs. was spotted at 3120' - with tubing at 2500'. Spotted 76 sxs. 60/40 pozmix - 10% gel - 200# hulls. Pulled tubing to 1381' - pumped 85 sxs. and 200# hulls to circulate cement to surface. T.O.H. Squeezed 5 1/2" casing with 35 sxs. Max. P.S.I. 700# held.

Remarks:  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL

I did  / did not  observe the plugging. Dennis L. Hamel

(agent)

**INVOICED**

DATE

5-18-95

INV. NO.

43851