

6030230

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-~~03~~30235-0020  
SE, SEC. 10, T. 9 S, R. 17 WE  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5247

Lease Name OSWALD Well # 3

Operator: OIL PROPERTY MAN. INC., County ROOKS  
Name & Address: 221 N. MAIN SUITE 200  
WICHITA, KANSAS  
67202

Well Total Depth 3449 112.09 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 77'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor OIL PROPERTY MANAG. INC. License Number 5247

Address AS ABOVE

Company to plug at: Hour: AM Day: 16 Month: 7 Year: 19 84

Plugging proposal received from DICK FINNESY

(company name) OIL PROP. MANAG. INC. (phone) \_\_\_\_\_

were: BOTTOM WAS SANDED OF TO 2964 WHERE TUBING WAS PARTED AND WELL STRIPPED - TUBING WAS TAGGED AT 2864 WHERE 20SX. CEM MIX. + 2SX. HULLS WERE SPOTTED - GOOD CIRC. - TUBING LAID DOWN TO 2500 WHERE 9 SX. GEL WERE SPOTTED - TUBING LAID DOWN TO 1350 WHERE CEM MIX. WAS CIRC. TO SURFACE 60SX. CEM MIX.

50/50 PZ 6 GEL 3% Plugging Proposal Received by Carl Goodrow (TECHNICIAN)  
2 SX. CENO FLAKE

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 PM Day: 16 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT AS ABOVE +

SHALE DEPTH 30'

BACKSIDE WAS PUMPED WITH 10 SX. CEM MIX. + 5 SX. HULLS - 8 SX. GEL - 25 SX. CEM MIX.

HALLIBURTON NO PLUG DROP.

Remarks: THERE WAS CEDAR HILL BREAK IN AT 1100'

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 7-31-84

Signed Carl Goodrow (TECHNICIAN)  
7/30/84 JUL 30 1984

INV. NO. 2787