

4- 041368

15-163-19 251-00-02

5-19

165
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-NA

W2 SE SE /4 SEC. 11, 09 S, 17 W
660 feet from S section line
990 feet from E section line

Operator license# 5363

Lease Westhusin well# 2

Operator: Berexco, Inc.

County Rooks

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3313 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe N/A Inch @ feet

107.67

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Titan License#

Address: Hays, Kansas 67601

Company to plug at: Hour: Day: 19 Month: May Year: 92

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: 7" casing set @ 3165' w/125 sx. cement. Perf. @ 3165' - 3303'.
Anhy. Perf. @ 1290'. Dakota @ 800'. 5 1/2" liner @ 3136' to 3313'.
Top liner 5 1/2" from surface to 1350'. Pulled 944' of 5 1/2" liner.
Ordered 800 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 7:30 P.M., Day: 19, Month: May, Year: 92

Actual plugging report: Run in hole with tubing to 1300'. Spot 300 sx.
cement with 500# hulls. P.O.O.H. with tubing. Hooked-up to 7" casing.
Squeezed 300 sx. cement w/500# hulls. Max. P.S.I. 200#. Shut in
P.S.I. 0#. W.L.M. / T.O.C. @ 350'. Perf. 7" casing @ 150' filled to
surface w/50 sx. cement. Hooked-up to 7" casing squeezed 80 sx. cement
to circulate cement at surface.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation:

I did X / did not observe the plugging.

DATE 6-2-92

INV. NO. 35394

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1992
(agent) 6-1-1992
CONSERVATION DIVISION
Wichita, Kansas