

4-041367

15-163-03122-00-00  
5-19  
166  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-NA  
NE SE SE /4 SEC. 11, 09 S, 17 W  
1980 feet from S section line  
660 feet from E section line

Operator license# 5363 Lease Westhusin well # 6

Operator: Berexco, Inc. County Rooks

Address: P.O. Box 723 Well total depth 3428 feet 111.41  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 318 feet  
w/200 sx.cmt.

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: B.J. Titan License#     

Address: Hays, Kansas 67601

Company to plug at: Hour:      Day: 19 Month: May Year: 92

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: 7" casing set @ 3428' w/200 sx. cement. Perf. @ 3145' - 3367'. P.B. 3381'. Baker packer at 3318'. 2 1/2" tubing 2948'. Rods @ 2718'. Hole in casing @ 806'. Ordered 550 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls plus 150 sx. common with 1/4# flocele.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [ X ], Part [      ], None [      ]

Completed: Hour: 6:45P.M., Day: 19, Month: May, Year: 92

Actual plugging report: Run in hole with tubing to 1300'. Spot 150 sx. common cement with 1/4# flocele. Pull tubing to 600'. Spot 110 sx. to circulate cement with 175# hulls. P.O.O.H. with tubing. Hooked-up to 7" casing. Squeezed 240 sx. cement with 225# hulls. Max. P.S.I. 200#. Shut in P.S.I. 100#. Hook-up to 10 3/4" S.P. Squeezed 25 sx. cement with 1/8" flocele mixed in cement. Max. P.S.I. 125#. Shut in P.S.I. 125#.

Remarks: Circulate 25 - 30 bbls. of fluid out of annulus.

Condition of casing(in hole): GOOD      BAD X Anhy.plug: YES X NO     

Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X NO     

Plugged through TUBING X, CASING     . Elevation:     

I did [ X ] / did not [      ] observe the plugging.

DATE 6-2-92

INV. NO. 35293

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 1 1992  
(agent) Dennis L. Hamel  
CONSERVATION DIVISION  
Wichita, Kansas  
6-1-1992