

15-163-19237-00-02

4-041591

7-26

E-24,057

API number: 15- - N/A

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE NE /4 SEC. 11, 09 S, 17 W
3630 feet from S section line
990 feet from E section line

Operator license# 8735

Lease Westhusin well # 5

Operator: S & M Oil Company

County Rooks

Address: 2904 Canal Blvd.
Hays, Kansas 67601

Well total depth 3415 feet ^{110.98}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 208 feet
w/125 sxs.

Aband. oil well __, Gas well __, Input well X, SWD __, D & A __

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 26 Month: July Year: 94

Plugging proposal received from: Steve Crawford

Company: S & M Oil Company Phone: _____

Were: 5 1/2" casing set @ 3415' w/1255 sxs. cement. Perf. @ 3130' -
3334'. W.L.M. 3090'. T.O.F. @ 1600'. Cemented from 2250' to surface
verified with bond log. Packer left in the hole at 3080'.
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00A.M., Day: 26, Month: July, Year: 94

Actual plugging report: Ran in the hole with tubing to 1736'. Pumped
in 25 sxs. cement, followed with 225 sxs. 60/40 pozmix - 10% gel with
500# hulls to circulate cement to surface. Max. 300#.

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1994
7-28-1994
CONSERVATION DIVISION
Wichita, Kansas

Remarks:
Condition of casing(in hole): GOOD X BAD ____ Anhy. plug: YES X NO ____
Bottom plug(in place): YES __, CALC X, NO ____ Dakota plug: YES X, NO ____
Plugged through TUBING X, CASING ____ Elevation: ____ GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED

DATE 7-28-94

INV. NO. 40924 SEP 28 1994