

6 040259

API NUMBER 15- 163-22,520-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NE, SEC. 18, T. 9 S, R. 17 W/EX
4950 feet from SE^X section line
330 feet from SE^{EX} section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8925

Lease Name Green-Iola Well # 1

Operator: Liberty Operations & Completion
Name: 309 West Mill
Address

County Rooks 115.38

Well Total Depth 3550 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8^{5/8} feet 259 w/150 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Pioneer Drilling License Number 5665

Address Plainville, Ks.

Company to plug at: Hour: AM Day: 9 Month: November Year: 19 84

Plugging proposal received from John Walker

(company name) Pioneer Drilling (phone) _____

were: Order 180 sks 50/50 pozmix 6% gel 3% cal cl., 1 sk hulls and 8^{5/8}" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good

circulation and no fluid loss.

RECEIVED
STATE CORPORATION COMMISSION
11-19-1984
NOV 19 1984

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 3:15 AM Day: 9 Month: November Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 1425 w/20 sks

2nd plug @ 800 w/100 sks w/1 sk hulls

3rd plug @ 275 w/40 sks

4th plug @ 40 w/10 sks Solid bridge

10 sks in Rat Hole Cemented by Allied

Remarks: _____

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 11-27-84

Signed Dennis Hamel
(TECHNICIAN)

4929

11-16-84
24

11-9