

6 040610 **PLUGGED**

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,879-00-00

SE SW NW SEC. 19, T 9 S, R 17 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 9087

Operator: American Lariat Inc.
Name & Address: 2970 Bear Valley Sq. IV,
250-6th Ave. SW
Calgary Alberta, Canada
T2P3H7

2970' feet from S section line
4290 feet from E section line

Lease Name Melhonic Well # 1
County Rooks 121.23

Well Total Depth 3730 feet

Conductor Pipe: Size - feet -

Surface Casing: Size 275' feet

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor R & C Drilling License Number _____

Address Hays, Kansas

Company to plug at: Hour: 9:30 AM Day: 26 Month: 4 Year: 19 86

Plugging proposal received from John Weiss

(company name) R & C Drilling (phone) _____

were: Ordered 215 sy 6 3/4 poz 60% gel, 4% cc
Circulated 1 hr. before plugging. Ran 10 bbls mud
flush, followed w/ cont. plug, followed w/ 3
bbls mud flush, pulled drill pipe above cont.
plug & circulated mud flush out of hole - con-
ditioned mud between plugs. Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:30 AM Day: 26 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT Spotted 25 sy @ 3600'

Filled Hole @ Mud 25 sy @ 1480'

" 100 sy @ 796' w/ 2 sy shells mixed in.

" 40 sy @ 350'

" 10 sy @ 40'

" 15 sy in Rat Hole

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE MAY 14 1986

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 13792