

6 020520

9-9

134 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,058-0000

SE. NE. SW. SEC. 29, T 9 S, R 19 W/E

1650 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428

Lease Name Ferland Well # 1

Operator Name Graves Drilling Co. Inc.

County Rooks 120.90

Address Box 8250

Well Total Depth 3720 feet

Wichita, Ks. 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well U&A x

Other well as hereinafter indicated

Plugging Contractor White and Ellis License Number 5420

Address

Company to plug at: Hour: 2:10 AM Day: 9 Month: 9 Year: 19 89

Plugging proposal received from Bob Kasper

(company name) White and Ellis (phone)

were: Order 200 sks 60/40 poz 6% gel 3% cal cl 1 sk f.c. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss. 60/40 - 6% w/1/4# lb. F.C. per sk of cement.

Plugging Proposal Received by *Gilbert Balchazor* (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 2:10AM Day: 9 Month: Sept Year: 19 89

ACTUAL PLUGGING REPORT

1st plug at 1600' w/25 sks

2nd plug at 1050' w/100 sks

3rd plug at 270' w/40 sks

4th plug at 40' w/10 sks behind wiper

15 sks in rathole 10 sks in mouse hole.

RECEIVED STATE CORPORATION COMMISSION

SEP 27 1989

9-27-89 CONSERVATION DIVISION (Wichita, Kansas)

Remarks: By Halliburton (If additional description is necessary, use BACK of this form.)

xxxxxx (did not) observe this plugging.

DATE 9-29-89

INV. NO. 25968

Signed *Gilbert Balchazor* (TECHNICIAN) Gilbert Balchazor