

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME McClay

WELL NUMBER 10

1880 Ft. from S Section Line

4400 Ft. from E Section Line

SEC. 12 TWP. 9S RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed 1/25/97

Plugging Commenced 12:00PM 1/25/97

Plugging Completed 3:30PM 1/25/97

LEASE OPERATOR S&M Oil

ADDRESS 2730 Thunderbird Drive Hays, Kansas 67601

PHONE# (913) 628-3658 OPERATORS LICENSE NO. 8735

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/24/97 (date)

by Dennis Hamel (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? No Log

Producing Formation None Depth to Top \_\_\_\_\_ Bottom T.D. 1632

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	213	8 5/8	213.43	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
1st Plug @ 1302' w/25sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes w/46 Vis Mud.  
2nd Plug @ 750' w/100sks 15sks In Rat Hole Plugs displaced with mud.  
3rd Plug @ 300' w/ 40sks Total 200sks 60/40 Poz 6%Gel & 3%CC By Allied Cementing  
4th Plug @ 40' w/10sks Completed @ 3:30PM 1/25/97  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: S&M Oil

STATE OF KANSAS COUNTY OF ELLIS, ss.

RECEIVED  
KANSAS CORPORATION COMMISSION  
1997 MAR - 6  
3/6/97

Steve Crawford

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Steve Crawford

(Address) 2730 Thunderbird Drive Hays, KS 67601

SUBSCRIBED AND SWORN TO, before me this 3rd day of March, 1997

Jeffery A. Schoenberger  
Notary Public

My Commission Expires: 10/17/98

