


15-163-00966-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 1 Twp. 9 Rge. 18 (E) W (W)
Location as "NE/CNW&SW" or footage from lines SE SE NW
Lease Owner Mallonee Drilling Company, Inc.
Lease Name Benedick Well No. 1
Office Address 812 Central Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5/26/ 1956
Application for plugging filed 5/26/ 1956
Application for plugging approved 5/26/ 1956
Plugging commenced 5/26/ 1956
Plugging completed 5/27/ 1956
Reason for abandonment of well or producing formation non-productive

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3530 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	125	8-5/8"	125	None-cement circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from 3530' to 122'. Plug set at 122'.
One-half sack Hulls, 15 sacks Cement, Mud to 40'.
Plug set at 40'. One-half sack Hulls, 10 sacks
cement to top of hole.


RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1956
CONSERVATION DIVISION
6-5-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallonee Drilling Company, Inc.
Address 812 Central Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. E. Mallonee (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Mallonee
812 Central Bldg., Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 31st day of May, 19 56
My Commission expires February 1, 1960
Barbara J. Layton
Notary Public.

PLUGGING
FILE SEC 1 T 9 R 18W
BOOK PAGE 66 LINE 30

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1956
CONSERVATION DIVISION
Wichita, Kansas
6-5-56

15-163-00966-00-00

DRILLERS' LOG
#1 Benedick
SE SE NW Sec. 1-9-18W
Rooks County, Kansas

OPERATOR: Mallonee Drilling Company, Inc.
CONTRACTOR: Mallonee Drilling Company, Inc.

COMMENCED: Cable Tool Surface
Hole 4/29/56
Rotary Under Surface
5/18/56
COMPLETED: 5/27/56

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	20	Post rock	
20	100	Grey Shale	
100	125	Blue Shale	8-5/8" surface casing set at 125' with 55 sacks common cement, set ahead with cable tools.
125	800	Shale and shells	
800	1100	Sand and shale	
1100	1390	Shale and shells	
1390	1425	Anhydrite	
1425	1445	Lime and shale	
1445	2010	Shale and shells	
2010	2145	Shale	
2145	2560	Lime and shale	
2560	2700	Lime and red bed	
2700	3198	Lime and shale	
3198	3339	Lime	
3339	3530	Lime and shale	
3530		Total depth of hole	D. & A.

I certify that to the best of my knowledge and belief the above represents a true and accurate Drillers' Log record of the captioned well.

R. E. Mallonee
R. E. Mallonee

State of Kansas)
County of Sedgwick)

Subscribed to and sworn to before me this 31st day of May, 1956.

My commission expires: Feb. 1, 1960

Barbara J. Layton
Barbara J. Layton, Notary Public

PLUGGING	
FILE SEC.	<u>1 T 9 R 18 W</u>
BOOK PAGE	<u>66 LINE 30</u>