


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-163-00784-00-00

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks County, Sec. 9 Twp. 9S Rge. 18 (E) W (W)
Location as "NE/CNWSW" or footage from lines NW SW SW
Lease Owner W. H. Pitts
Lease Name Levi Holl Well No. 1
Office Address 413 Parkview, Jonesboro, Arkansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Oct. 22, 1960
Application for plugging filed Oct. 22, 1960
Application for plugging approved Oct. 22, 1960
Plugging commenced Oct. 22, 1960
Plugging completed Oct. 22, 1960
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3575 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	220'	8-5/8"	220'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3575' to 550' - heavy rotary mud
550' to 488' - plug, 1/2 sk. hulls and 20 sacks cement
488' to 180' - heavy rotary mud
180' to 134' - plug, 1/2 sk. hulls and 15 sacks cement
134' to 40' - heavy rotary mud
40' to 6' - plug, 1/2 sk. hulls and 10 sacks cement
6' to 0 - cellar

RECEIVED
STATE CORPORATION COMMISSION

JAN 29 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PEEL BROTHERS, INC. 1-20-61
Address P.O. Box 359, Hoisington, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.
Peel Brothers, Inc. (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) BY Jack Matthews
P.O. Box 359, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of October, 19 60

My commission expires April 27, 1964 Luth Brank Notary Public.



DRILLERS' LOG

Well Owner: W. H. Pitts NW SW SW
 Farm Name: Levi Holl Well No. 1 Sec. 9, Twp. 9S, Rge. 18W,
 Total Depth: 3575' County: Rooks, Kansas
 Commenced: 10/13/60
 Completed: 10/22/60
 Casing: 2-5/8" @ 220' cem. Elevation:
 Contractor: Peel Brothers, Inc. Production: Dry

Figures below indicate bottoms of formations:

Surface soils	0 -	30
Sand and shale		221
Shale and shells		945
Shale and sand		1090
Sand		1175
Lime, shells and shale		1290
Shale and sand		1450
Anhydrite		1480
Shale		1590
Shale and shells		2125
Shale and lime		2300
Lime		2410
Shale		2430
Lime		2495
Lime and shale		2625
Shale and lime shells		2730
Shale and lime		3070
Lime		3575
Total Depth		3575

Stamp: J.A. ...
 CORRECTION ...
 1-20-61

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: Jack Mattick

SUBSCRIBED AND SWORN to before me this 24th day of October, 1960

My commission expires: April 27, 1964

Rich Brant
Notary Public

