

API NUMBER 15-163-22,396  
 LEASE NAME Pope  
 WELL NUMBER 1  
 SPOT LOCATION 40' S of E/2 W/2  
 SEC. 9 TWP. 9 RGE. 18 <sup>SW</sup> or (W)  
 COUNTY Rooks  
 Date Well Completed 6-3-84  
 Plugging Commenced 6-3-84  
 Plugging Completed 6-4-84

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR H K & W Operating  
 ADDRESS P.O. Box 1851 Salina, KS 67401

PHONE # (316) 792-7327 OPERATORS LICENSE NO. 6280

Character of Well D&A  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays Kansas

to be filed by  
 Is ACO-1 filed? operator If not, is well log attached? yes

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.  
Bottom Plug: @ 1466' w/20 sacks 50/50 pozmix 2% gel 3% cc. thru drill pipe  
Next Plug: @ 845' w/100 " " " " & 1 sack Cello Flake  
Next Plug: @ 340' w/40 sacks " " " thru drill pipe  
Top Plug: @ 40' w/solid bridge of 1/2 sack hulls & 10 sacks cement 10sx in rat hole  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929  
 Address P.O. Box 823 Great Bend, KS 67530

RECEIVED  
 STATE CORPORATION COMMISSION  
 6-19-84  
 JUN 19 1984  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

Bill Draney (employee of operator) or  
~~XXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill Draney  
 (Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 11 day of June, 1984

Alouise M. Hague  
 Notary Public



My Commission expires 4-29-86

DRILLER'S WELL LOG

DATE COMMENCED: May 30, 1984  
DATE COMPLETED: June 3, 1984

H K & W Operating  
POPE #1  
40' S of E/2 W/2 SW  
Sec. 9, T9S, R18W  
Rooks County, Ks.

0 - 960' Surface soil, Shale, Post Rock  
960 - 1466' Sand & Red Bed  
1466 - 1506' Anhydrite  
1506 - 3025' Lime & Shale  
3025 - 3237' Lime  
3237 - 3241' Shale  
3241 - 3262' Lime & Shale  
3262 - 3503' Lime  
3503 - 3550' Shale, Lime, Chert, Sand  
3550' RTD

ELEVATION: @2068' KB

FORMATION DATA

Cedar Hill 960'  
Anhydrite 1466'  
Topeka 3025'  
Heebner 3237'  
Toronto 3262'  
Lansing 3288'  
Base K.C. 3503'  
Marmaton 3511'  
Conglomerate 3520'  
RTD 3550'

Surface Pipe: Set new 8-5/8"  
20# pipe @298' w/175 sacks  
50/50 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 11 day of June 1984.

My Comm. Expires:

4-29-86

Dorothy M. Hague  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1984

CONSERVATION DIVISION  
Wichita, Kansas

6-19-84